

# CERN Lab Talk

## Current and Future Projects Recent LLRF achievements and challenges

Wolfgang Hofle

CERN AB/RF/FB


LLRF: AB-RF-FB and AB-RF-CS Sections  
Special thanks to M.E. Angoletta, P. Baudrenghien, J. Molendijk,  
V. Rossi, D. Valuch

# Outline

- Overview of CERN accelerators and the LHC Injector chain
- LHC Project status and plans for commissioning
- Transverse feedbacks
- LHC Ions Injector chain: Recent Progress and LLRF issues
- Upgrade plans for the LHC injector chain
- Summary and what's been omitted

# Current CERN Accelerator Complex

**LHC: 177 GeV/n to 2.76 TeV/n, ions**  
**450 GeV to 7 TeV, protons**  
**400, [ 200 ] MHz**



**SPS: 5.9 to 177 GeV/n, ions**  
**26 to 450 GeV, protons**  
**200, 800 MHz**

**AD: 3.5 to 0.1 GeV/c, antiprotons**  
**0.17-1.6, 9.5 MHz**

**PSB: 50 MeV to 1.4 GeV, protons**  
**0.6-1.7, 1.2 - 3.4, 6 - 17 MHz**

**LEIR: 4.2 to 72 MeV/n, ions**  
**0.7-4.7 MHz**

**PS: 72 MeV/n to 5.9 GeV/n, ions**  
**1.4 to 26 GeV, protons**  
**3-10, 13/20, 40, 80, 200 MHz**

**CFT3 Electrons**  
**3, 30 GHz**

▶ p [proton] ▶ ion ▶ neutrons ▶  $\bar{p}$  [antiproton] ▶ proton/antiproton conversion ▶ neutrinos ▶ electron


LHC Large Hadron Collider SPS Super Proton Synchrotron PS Proton Synchrotron

AD Antiproton Decelerator CFT3 Clic Test Facility CNGS Cern Neutrinos to Gran Sasso ISOLDE Isotope Separator OnLine DEvice

LEIR Low Energy Ion Ring LINAC LINear ACcelerator n-ToF Neutrons Time Of Flight

# LHC Project Status and plans for commissioning

# LHC Status and plans for 2008



LHC start-up with beam May 2008

Injectors will start-up spring 2008, LHC beams lead start-up

Start-up of LHC with beam scheduled for 21<sup>st</sup> May 2008

Commissioning of LHC LLRF and transverse dampers with beam 2008



Cavities + RF system  
& Transverse Dampers  
are all in point 4

**hardware commissioning coo**


**INTRO** | **NONCONFORMITIES** | **SCHEDULES** | **TYPICAL HC PROGRAMME** | **ACCESS** | **TEAM** | **REGULAR ME**

- **MAIN PAGE**
- **TWIKI**
- **WORKSHOPS**
- **MEETINGS**
- **MTF**
- **DOCUMENTS**

**sector 45**  
The left part of the sector (from IP4 to 17L5) is floating around 90K while the rest is being cooled down from room temperature. As soon as this part reaches 80K (foreseen for the end of week 42) the sector will be cooled down all together to 1.9K. Due to the particular conditions, the access to the left part of the sector is limited while the access to point 5 is forbidden. As soon as the second phase of the cool down starts the access will be restricted but possible in all the sector.

**sector 56**  
After the successful pressure test, carried on at the end of w.38, the last days of last

### Cryo main page - Sector 45



# LHC Status and plans

- LHC has 8 sectors to cool down and commission (~27 km)
- Sector 7-8 cool-down and powering tests for 450 GeV done, now warmed up again
- Sector 4-5 cool down started, expected at LHe in November 07
- RF Cavity cool down to start in November 2007
- RF getting ready for cavity conditioning, see talk by [J. Molendijk](#) (Monday pm)
- LHC Lowlevel RF to be presented by [P. Baudrenghien](#) (Tuesday am)
- Staged commissioning with varying bunch patterns

Machine parameters		450GeV Target	Stage A		Stage B		Stage C		Stage D	
			Target	Limit	Target	Limit	Target	Limit	Target	Limit
spacing	ns	2021	2021	588	75	75	25	25	25	25
bunch length	m	0.1124	0.0755	0.0755	0.0755	0.0755	0.0755	0.0755	0.0755	0.0755
crossing angle	urad	0	0	0	250	250	285	285	285	285
bunch intensity		4.00E+10	4.00E+10	9.00E+10	4.00E+10	9.00E+10	5.00E+10	5.00E+10	9.00E+10	1.15E+11
bunches		43	43	158	936	936	2908	2908	2908	2908
energy	eV	4.50E+11	7.00E+12							
F		1.00	1.00	1.00	0.96	0.92	0.90	0.84	0.90	0.84
normalised emittance	cm	3.76E-04	3.75E-04							
beta*	cm	1100	200	200	200	100	100	55	100	55
luminosity	/cm <sup>2</sup> s	7.18E+28	6.12E+30	1.12E+32	1.29E+32	1.24E+33	1.13E+33	1.01E+33	3.85E+33	1.01E+34
total incl cross section	cm <sup>2</sup>	6.00E-28	8.00E-28							
event rate per cross		0.01	0.75	3.85	0.73	7.09	2.14	3.53	0.94	19.18
protons per beam		1.72E+12	1.72E+12	1.40E+13	3.74E+13	8.42E+13	1.40E+14	1.40E+14	2.53E+14	3.23E+14
current per beam	mA	3.09E+00	3.09E+00	2.53E+01	6.74E+01	1.52E+02	2.53E+02	2.53E+02	4.55E+02	5.81E+02
energy per beam	Joules	1.24E+05	1.83E+09	1.57E+07	4.19E+07	9.43E+07	1.57E+06	1.57E+06	2.83E+08	3.62E+09
beam size	um	293.3	31.7	31.7	31.7	22.4	22.4	16.6	22.4	18.8



Commission hardware for high energy operation

In stabilisation of phase at collimators and full beam dump diluters

<http://lhccwg.web.cern.ch/lhccwg/>

# Transverse Feedbacks

# LHC Transverse Feedback System



## Beam parameters and requirements for nominal intensity:

Injection beam momentum	450 GeV/c
Static injection errors	2 mm (at $\beta_{\max}=183$ m)
ripple (up to 1 MHz)	2 mm (at $\beta_{\max}=183$ m)
resistive wall growth time	18.5 ms
assumed de-coherence time	68 ms
tolerable emittance growth	2.5 %
Overall damping time	4.1 ms (46 turns)
bunch spacing	25 ns
minimum gap between batches	995 ns
lowest betatron frequency	> 2 kHz
highest frequency to damp	20 MHz
choice:	“electrostatic kickers” (“base-band”)
aperture	52 mm
kickers per beam and plane	4
length per kicker	1.5 m
nominal voltage up to 1 MHz at $\beta=100$ m	+/- 7.5 kV
kick per turn at 450 GeV/c	2 $\mu$ rad



## Currently *installed* transverse feedback systems in CERN Synchrotrons

Accelerator	Digital / analogue processing	Power / kicker / bandwidth	Usage in operation
<b>PS Booster</b> (protons) 50 MeV – 1.4 GeV kin. E.	multi turn injection from Linac 2 analogue beam offset signal suppression, analogue delay (cables & switches)	100 W, 50 $\Omega$ stripline Limited to 13 MHz in operation But built for 100 MHz bandwidth, baseband	H-plane: <b>used and required</b> V-plane: beam stable w/o FB
<b>AD</b> (anti-proton decelerator) 3.57 GeV – 0.1 GeV	Copy of booster system	100 W, 50 $\Omega$ stripline 100 MHz bandwidth baseband	used only for excitation purposes
<b>SPS</b> (protons, ions) (14 – 450) GeV/c protons FT (26 – 450) GeV/c LHC beam	digital notch filter and 1T-delay (Altera FPGA, 80 MHz clock) commissioned in 2000/2001	tetrode amplifiers with two 30 kW tetrodes in push-pull directly coupled to a kicker (base band); feedback bandwidth ~10 kHz to 20 MHz	H-plane: used in operation V-plane: used in operation <b>used and required for operation</b> above $5 \times 10^{12}$ protons (max $\sim 5.5 \times 10^{13}$ ppp accelerated)

## Current transverse feedback system *projects* at CERN

Accelerator	Digital / analogue processing	Power / kicker / bandwidth	Planned commissioning and usage
<b>LEIR</b> ( ions: Pb <sup>54+</sup> ) 4.2 MeV/u – 72 MeV/u	copy of PS Booster System New: remote control of pick-up vector sum	100 W, 50 $\Omega$ stripline	<b>2007</b> Commissioned
<b>PS</b> (protons, ions) 1.4 GeV – 25 GeV (kinetic E)	synergy with LHC Damper for The low level digital processing	2 kW solid state power amplifier; 112 $\Omega$ stripline (0.9 m length), planned with ~30 MHz bandwidth in baseband, lower cut-off ~50 kHz	<b>2008</b> injection damping and feedback will be beneficial in particular for high intensity CNGS beams and LHC beams. Currently horizontal instabilities are cured by introducing coupling to the vertical plane which constrains the tunes
<b>LHC</b> (protons, ions) protons: 450 GeV/c – 7 TeV/c	digital notch filter and 1T-delay, built-in diagnostics 14 bit DAC Altera FPGA, 40/80 MHz clock new development in progress	tetrode amplifiers with two 30 kW tetrodes in push-pull directly coupled to kicker (base band) similar to SPS system 3 kHz -> 20 MHz	<b>2008</b> injection damping feedback loop closed during ramp switch off during physics?

## Progress with Ions for LHC

# I-LHC Project (ions for LHC)




Plan: LHC to collide  $Pb^{82+}$  ions 2009

Later also lighter ions

LEIR commissioned 2005  
new fully digital beam control system  
collaboration with BNL


2006: Pb commissioning started in PS  
dedicated LLRF system based on PS  
LLRF for LHC protons (MDDS,  
Multi-harmonic sources, tagged clock

2007: Acceleration of Pb ions in SPS  
with new MDDS and SDDS (based  
on LHC LLRF developments)  
Fixed frequency acceleration



Ions for LHC – bold blue line (Linac3-LEIR-PS-TT2-TT10-SPS-LHC)

## I-LHC injector chain from LEIR to LHC




$$891 = 8x(4b+1.25e)+7.75e + 2x[13x(4b+1.25e)+7.75e] + 3x\{12x(4b+1.25e)+7.75e+2x[13x(4b+1.25e)+7.75e]\} + 21e$$



**LHC**

LHC harmonic number (~400.8 MHz)  $h = 35640 = 10x4x891$   
 592 bunches in 891 bunch places  
 gaps between batches injected from SPS: 1000 ns (9 missing bunches) abort gap: 30 missing bunches (3.1 ms)

**SPS**



SPS batches: 13x4, 12x4, 8x4  
 gaps between batches injected from PS: 225 ns (1.25 missing bunches)

**PS**



PS: 4 bunches: spacing ~100 ns

**LEIR**



LEIR: 2 bunches

Early scheme LHC (62x62): 2444 4444 4444 4444  
 Bunch spacing 1.350 ms (source: R. Bailey, LHC MAC June 05)

magnetic alloy-based (Finemet®), wide-band, non-tunable cavity

Dual harmonic operation *on a single cavity* ( $h, 2h$ )

Cavity servo-loop to be tuned on  $h$  &  $2h$

Real-time control of gap relay to short-circuit cavity

High cavity voltage dynamic range (~60 dB)

Early operation:  $h = 1 \rightarrow f_{RF,MIN} = 0.36$  MHz


Nominal operation:  $h = 2$

$f_{RF}$  0.7 – 2.8 MHz for Pb54+

$f_{RF}$  0.7 – 5 MHz for lighter ions

## Beam control features:

- Frequency program.
- Phase/radial/synchro loops (DSP)
- Radial steering, frequency offset etc.
- Bunching after injection(s) & acceleration on same cycle.
- RF trains generation...



LEIR cavity impedance  $Z$

M.-E. Angoletta

Daughter cards development continues:




**4 channel 14 bit  
ADC AD 9245BCP-  
80 (80 MHz max)**

**NEW:  
2 MB/10 ns (instead  
of 500k/12ns) SRAM  
(1 M x 16 bits)**

**Altera Stratix  
EP1S20F484C5  
(instead of EP1S10)**

DDC digital down converter daughter card

SDDS Slave DDS daughter card




**4 channel 14 bit DAC AD  
9754BCP-80 (125 MHz max)**

**NEW:  
2 MB/10 ns (instead of 500k/12ns)  
SRAM (1 M x 16 bits)**

**Altera Stratix EP1S20F484C5  
(instead of EP1S10)**


A. Blas




LEIR digital BC system crate & hardware

DSP carrier board with daughter cards

**MDDS with AD9858 1GHz clock DDS**



Start-up of LEIR LLRF with O<sup>4+</sup>



Beam capture - tomoscope  
“Waterfall” plot.

2005 Start of LEIR Beam commissioning, Digital LLRF


2006 LEIR providing early beam to PS

2007 LEIR operationally running with early beam for SPS commissioning; running for PS commissioning for nominal beam; work on LEIR software integration and cavity servo loops continues

M.-E. Angoletta

Pb Ions are heavy – and slow

# SPS LLRF Challenges: Ions for LHC




SPS Traveling wave cavity system  
Center frequency 200.22 MHz  
Bandwidth +/- 500 kHz

# Transfer of ions from PS to SPS



Frequency swing too large for unique h in SPS during acceleration!

PS-SPS: choice of harmonic numbers and limits from SPS 200 MHz TWC system

423 = 9 × 47  
4653 = 11 × 423




# Scheme for accelerating ions for LHC in the PS




PS Ions for LHC LLRF: J.-L. Vallet / M. Schokker

Beam Current Profiles




Simulation

Measurement



S. Hancock





Phase error for outermost bunches:

$$\frac{1}{2} \times 2\pi \times 423 \times \left[ \frac{3 \times 8}{169} - \frac{3 \times 20}{423} \right] = 12.78^\circ$$

# Fixed frequency (constant harmonic number) acceleration in SPS for LHC ions

*Frequency swing too large for unique h in SPS during acceleration !*







MDDS and SDDS with AD9959

- 1) Injection:  $f_1 = 4653 \times f_{\text{REV}} \sim 199.98 \text{ MHz}$   $f_2 =$
- 2) After injection: compress batch by moving  $f_1$  to 200.22 MHz (TWC center frequency)
- 3) Switch to radial loop and accelerate keeping  $f_1 = 200.22 \text{ MHz}$  *constant*.  $f_2$  will increase during acceleration;  $\langle f_{\text{RF}} \rangle = 4620 \times f_{\text{REV}}$ ;  $f_{\text{RF}}$  is modulated but features always exactly 4620 periods per turn in a phase continuous way
- 4) When  $f_1 = f_2$  (@transition) continue acceleration without FSK modulation  $f_{\text{RF}} = f_1 = f_2 = \langle f_{\text{RF}} \rangle = 4620 f_{\text{REV}}$  will increase
- 5) Lock on LHC RF frequency with synchro loop at top energy
- 6) Rephasing with LHC common frequency  $f_c$  (maximum 1/14 of SPS circumference) will take <500 ms
- 7) Fine synchronization @ 200 MHz and extraction


Postponed to 2009



T. Bohl


# Future upgrades to the proton injectors

# Future Upgrades to CERN Accelerator Complex [5]



R. Garoby

# Future Upgrades to CERN Accelerator Complex [5]




LINAC 4 is an approved project: Construction 2008-2011  
SPL and PS2: Studies ongoing, construction ~ 2012-2016  
Consolidation of PSB, PS, SPS LLRF required

PS2, 4 -> ~ 50 GeV protons (and ions)  
1346 m circumference  
20 - 40 MHz (?)

SPL 180 MeV – 4/5 GeV  
704 MHz

LINAC4: H-, 160 MeV  
[upgrade to 180 MeV]  
352 MHz

## Linac4 updated design




1x10<sup>14</sup> H<sup>-</sup> / per pulse, 2 Hz repetition rate

F. Gerigk et. al. [7]


Future extension for SPL; for PS2: 1.5x10<sup>14</sup> H<sup>-</sup> / per pulse (1.2 ms)

## Linac4 (160 MeV)

## SC-linac (4/5 GeV)




# Front end for LINAC4 (3 MeV test stand)



C. Rossi [8]

# 3 MeV test stand and LINAC4 Low Level Proposal



LL Hardware:  
similar to LHC but  
at 352.2 MHz

- tuner loop
- FB (dig. only)
- Feed-forward or 1-shot delay FB

Implementation:  
same VME crate as  
LHC, 1 crate/Klystron

Challenge:  
phase stability  
of RF distribution  
re-use LEP fibers  
(temp. stabilized)

P. Baudrenghien [8]

## Summary

LHC en route for commissioning with beam in 2008

LHC TFB LL is based on LHC LLRF developments, migration to TFBs in other accelerators foreseen

Important progress with acceleration of ions in injectors

- New digital LLRF for LEIR successfully commissioned

- PS acceleration of Pb ions with newly configured beam control, PS RF gymnastics for ions

- SPS: Deployment of LHC based LLRF hardware for acceleration of ions successful

Upgrade of injector chain: LINAC4 project has been approved, proposal for LLRF based on LHC LLRF

For future LLRF systems:

Continue trend towards generic solutions for groups of accelerators

*Not covered by presentation, but equally important*

High intensity protons for CNGS

Linac2 and Linac3

AD

CLIC and CTF3 (see CLIC Workshop October 2007 [9])

## References

- [1] P. Baudrenghien et.al.: *The LHC Low Level RF System*, LLRF07 Workshop, Knoxville, TN, 2007
- [2] O.S. Bruning (Ed.), LHC Design Report, chapter 6: *The RF System and RF Beam Feedback*,  
[https://edms.cern.ch/file/445835/4/Vol\\_1\\_Chapter\\_6.pdf](https://edms.cern.ch/file/445835/4/Vol_1_Chapter_6.pdf), CERN-2004-003-V-1
- [3] S. Maury et al., *Ions for LHC: Beam Physics and Engineering Challenges*, PAC05, Knoxville, USA, May 2005
- [4] M.E. Angoletta et al.: *Beam Tests of a New Digital Beam Control System for the CERN LEIR Accelerator*, PAC 2005, Knoxville, TN, USA, 16 - 20 May 2005, LHC Project Report 817
- [5] R. Garoby, *Plans for Upgrading the CERN Proton Accelerator Complex*, CERN-AB-2007-074 PAF, 2007
- [6] R. Garoby, F. Gerigk: *Status of the SPL at CERN*, CERN-AB-2007-016-RF, 2007
- [7] F. Gerigk et. al., *RF Structures for Linac4*, PAC2007, paper FROBC02
- [8] F. Gerigk, M. Vretenar [Ed]: *Linac4 Technical Design Report*, CERN-AB-2006-084 ABP/RF, 2006
- [9] H. Braun (chair): *Clic Workshop*, CERN 16-18 October 2007  
<http://indico.cern.ch/conferenceDisplay.py?confId=17870>